

**ADDENDUM NO. 1**  
**September 11, 2024**

**PROJECT: CITY OF KEENE**  
**FAIRVIEW STREET RECONSTRUCTION**

**BID DATE: SEPTEMBER 18, 2024**

The following changes and/or additions shall be made to the Plans, Specifications, and Contract Documents for the above referenced project. Bidder shall acknowledge receipt of this Addendum by signing below and returning this Addendum with the Bid.

- 1) **Cement stabilization of the subgrade shall be used in lieu of lime on this project. The cement shall be applied according to the NCTCOG Specification Item 301.3. Portland Cement Treatment at a rate of 4%. Reference to “lime treatment” in the bid schedule shall be replaced with “cement treatment”.**
- 2) **The entire street width may be reconstructed at once, however, access to residents on the street must be maintained at all times.**
- 3) **The 6” base coarse shall consist of the road-mixed material.**
- 4) **The depth of the curb gutter shall be 7”.**
- 5) **The curb transition at driveways shall match the gutter profile. Existing driveways shall be sawcut along the gutter line and concrete replaced to transition into existing curb return.**

Prepared by:

**JACOB | MARTIN**  
**TBPE Firm No. 2448**

\_\_\_\_\_  
**Bidder’s Acknowledgment**

\_\_\_\_\_  
**Date**



9/11/24