

ADDENDUM NO. 1
March 31, 2025

PROJECT: CITY OF AZLE
VAC-TRUCK BUILDING

BID DATE: APRIL 3, 2025 AT 3:00 PM

The following changes and/or additions shall be made to the Plans, Specifications, and Contract Documents for the above referenced project. Bidder shall acknowledge receipt of this Addendum by signing below and returning this Addendum with the Bid.

- 1) Dead Load (In addition to the weight of the structure) = 3 psf. Also, Roof Collateral Load = 5 psf. Below are some examples of how these loads are typically used in ASD load combinations. These two load combinations are not a complete list of the required load combinations.

Dead + Collateral + Live
 $0.6 * \text{Dead} + 0.6 * \text{Wind}$

- 2) Please note that the exterior wall panel along Grid 3 is full height. However, an interior wall liner panel is not required.
- 3) A fire rating of 90 minutes is acceptable for walk-in doors. The overhead door does not have to be fire rated.
- 4) The overhead door should have a manual crank with a chain hoist.
- 5) AISC and MBMA certifications are not required if the requirements of the construction documents are met.
- 6) All earthwork will be performed by the City except fine leveling for the slab and trenching for drains and footings.
- 7) Insulation will only be required in the enclosed room.

Prepared by:

JACOB | MARTIN
TBPE Firm No. 2448

Bidder's Acknowledgment

Date