

ADDENDUM NO. 3
April 3, 2024

PROJECT: CITY OF SNYDER
WTP – SEDIMENTATION BASIN IMPROVEMENTS AND WWTP – UV
DISINFECTION IMPROVEMENTS - REBID

BID DATE: April 10, 2024, 2:00 PM

The following changes and/or additions shall be made to the Plans, Specifications, and Contract Documents for the above referenced project. Bidder shall acknowledge receipt of this Addendum by signing below and returning this Addendum with the Bid.

Plans:

1. Sheet WW-3: Jib Crane Note 1 shall be **revised** to read as follow:

“Jib crane and hoist shall be ½ ton Harrington Foundationless Jib Crane and Hoist Kit, Model 350F-1000-08-11 supplied by L.K. Goodwin & Co., or equal. Jib crane shall have a height under boom of 11’-0” and span of 8’-0”. Hoist shall be 3-phase dual speed VFD electrically operated with motorized trolley.”

2. Sheet WW-3: Jib Crane Notes 2 and 3 shall be **deleted**.
3. Sheet WW-3: Jib Crane Note 4 shall be **deleted**. The City has removed the existing ductwork from the room to allow for more headroom for the jib crane and hoist. Maximum allowable headroom for the jib crane is 11’-10”.

Prepared by:

JACOB | MARTIN

Bidder’s Acknowledgment

Date