



**ADDENDUM NO. 1  
June 20, 2022**

**PROJECT: CITY OF BIG SPRING  
6-INCH WATER LINE – GAS PIPELINES HORIZONTAL DIRECTIONAL  
DRILL**

**BID DATE: June 29, 2022, 3:00 PM**

The following changes and/or additions shall be made to the Plans, Specifications, and Contract Documents for the above referenced project. Bidder shall acknowledge receipt of this Addendum by signing below and returning this Addendum with the Bid.

**GENERAL**

1. Clarification: The scope of work for this project is shown on Plan Sheet 3 of the drawings and includes the 450 LF of horizontal directional drill for the 6” water line. The Contractor shall be responsible for the following construction activities associated with the directional drill:
  - Contractor shall be responsible for supplying the 6” HDPE pipe for the bore.
  - Contractor shall be responsible for fusing HDPE pipe.
  - Contractor shall be responsible for locating and verifying depths of all gas lines prior to completing bore.
  - Contractor shall be responsible for contacting all the gas line companies prior to completing the bore.
  - Contractor shall be responsible for performing a hydrostatic test of the installed HDPE pipe. Pipe shall be tested to 150 psi.
  - Contractor will NOT be responsible for making connections to city installed pipe at each end of the bore. City will make connections to the pipe.
  
2. Clarification: Contractor may supply and install DR11 IPS HDPE pipe instead of the DR11 DIPS HDPE pipe shown on the drawings.

**Prepared by:**

**JACOB | MARTIN  
TBPE Firm No. 2448**

\_\_\_\_\_  
**Bidder’s Acknowledgment**

\_\_\_\_\_  
**Date**