ADDENDUM NO. 1 ISSUED: JANUARY 22, 2025

PROJECT: CITY OF ANSON

WATER TREATMENT PLANT DISINFECTION IMPROVEMENTS RE-BID

BID DATE: JANUARY 29, 2025 AT 3:00 PM

The following changes and/or additions shall be made to the Plans, Specifications, and Contract Documents for the above referenced project. Bidder shall acknowledge receipt of this Addendum by signing below and returning this Addendum with the Bid.

1) **GENERAL**

- a) The proposed chlorine dioxide generator requires 220VAC, single phase power, however the City's existing panel "MDP" provides 480V, three phase power. The Contractor shall be responsible for supplying 480V, three phase power to the control panel on the generator skid. The generator skid will be equipped, from Evoqua, with the appropriate transformer to account for the 480V, three phase supply. The Contractor is to verify the control panel breaker size with Evoqua and adjust the breaker size in panel "MDP", conduit, and wiring as necessary per NEC code.
- b) The OWNER will set and anchor the 1,400 gal LAS bulk storage tank.
- c) Level indication for the LAS bulk storage tank will be provided and installed by OWNER, and shall consist of Item 2.4.A. and Item 2.4.C. from Specification 11 03 01 VERTICAL HIGH DENSITY CROSSLINKED POLYETHYLENE STORAGE TANKS.
 - A. Float Indication: The level indicator shall be assembled to the tank and shall consist of PVC float, indicator, polypropylene rope, perforated interior pipe, PVC roller guides, clear PVC sight tube and necessary pipe supports. The level indicator shall act inversely to the tank contents and shall not allow entrance of tank contents into the sight tube at any time.
 - C. Physical Markings: Bulk storage tanks shall have a level mark with numerical value on the exterior of the tank at 1 foot increments. Day tanks shall have level mark and numerical value at 6 inch increments.

	Prepared by:
Bidder's Acknowledgment	JACOB MARTIN
	TBPE Firm No. 2448
	11
Date	Lit Jarle
	TE OF TELL
	9
	HENRY K. HARLE
	98381 : P
	CENSE
	SONAL ENG