

**ADDENDUM NO. 1
NOVEMBER 25, 2024**

**PROJECT: MILLSAP WSC
CID 01 - ARPA DISTRIBUTION SYSTEM IMPROVEMENTS**

BID DATE: DECEMBER 5, 2024 AT 2:00 PM

The following changes and/or additions shall be made to the Plans, Specifications, and Contract Documents for the above referenced project. Bidder shall acknowledge receipt of this Addendum by signing below and returning this Addendum with the Bid.

1. Air valve locations as shown on SHEET 04 are approximate, contractor to field locate existing distribution lines and install air valve at high point on existing line.
2. Air valves shall be combination air valve per specification 33 02 08 Air Valves section 2.4 Combination Air Valve.
3. Contractor must be able to provide proof of active SAM.gov registration within 2 weeks of bid opening and shall maintain SAM.gov registration active throughout the duration of this project.
4. The attached revised bid schedule shall be used.

Prepared by:

**JACOB | MARTIN
TBPE Firm No. 2448**

Bidder's Acknowledgment

Date

**MILLSAP WSC
CID 01 - ARPA DISTRIBUTION SYSTEM IMPROVEMENTS
BASE BID SCHEDULE**

Show prices in numerals. Round off unit prices to two decimal places only.

These Bid Prices must include all labor, materials, equipment, insurance, overhead, superintendence, transportation, taxes, permits, profits & incidentals to cover the finished Work called for in the Contract Documents.

For all Labor, Materials, Equipment and Incidentals to Furnish and Install the Following:

Bid Item	Description	Est. Qty.	Unit	Unit Price	Extended Amount
1	Mobilization, Bonds, and Insurance	1	LS	\$	\$
2	8" CL200 (SDR 21) PVC Water Line	750	LF	\$	\$
3	4" CL200 (SDR 21) PVC Water Line	4,500	LF	\$	\$
4	14" Bore & Encasement	60	LF	\$	\$
5	10" Bore & Encasement	140	LF	\$	\$
6	4" Bore & Encasement	150	LF	\$	\$
7	Service Meter Reconnect (Long, Excluding 4" Bore & Encasement)	5	EA	\$	\$
8	Service Meter Reconnect (Short)	13	EA	\$	\$
9	4" x 1" Tapping Saddle & Tapping Valve	3	EA	\$	\$
10	8" Gate Valve & Box	5	EA	\$	\$
11	4" Gate Valve & Box	4	EA	\$	\$
12	2" Gate Valve & Box	2	EA	\$	\$
13	1" Air Valve on Existing Line	21	EA	\$	\$
14	1" Air Valve on New Line	4	EA	\$	\$
15	2" Flush Valve	5	EA	\$	\$
16	Existing Water Line Connection (2-inch or smaller)	2	EA	\$	\$
17	Existing Water Line Connection (larger than 2-inch)	3	EA	\$	\$
18	Waterline Marker	8	EA	\$	\$
19	Metal Detectable Tape	5,250	LF	\$	\$
20	Owners Allowance	1	LS	\$ 145,000.00	\$ 145,000.00
TOTAL BASE BID (Items 1 - 20)					\$

MILLSAP WSC
CID 01 - ARPA DISTRIBUTION SYSTEM IMPROVEMENTS
DEDUCTIBLE ALTERNATE BID SCHEDULE

Show prices in numerals. Round off unit prices to two decimal places only.
 These Bid Prices must include all labor, materials, equipment, insurance, overhead, superintendence,
 transportation, taxes, permits, profits & incidentals to cover the finished Work called for in the Contract Documents.

For all Labor, Materials, Equipment and Incidentals to Furnish and Install the Following:

Bid Item	Description	Est. Qty.	Unit	Unit Price	Extended Amount
DA1	1" Air Valve on Existing Line	21	EA	\$	\$
TOTAL DEDUCTIBLE ALTERNATE BID (Item DA1)					\$

Note: Owner reserves the right to accept any combination of base bid and deductible alternate bid items.