



**ADDENDUM NO. 2**  
**September 8, 2023**

**PROJECT: CITY OF BIG SPRING**  
**BIRDWELL LIFT STATION**

**BID DATE: September 13, 2023**

The following changes and/or additions shall be made to the Plans, Specifications, and Contract Documents for the above referenced project. Bidder shall acknowledge receipt of this Addendum by signing below and returning this Addendum with the Bid.

**1) GENERAL**

- a. Spent water from dewatering activities may be discharged into Beals Creek.
- b. There are no AIS requirements on this project.
- c. The City does not require construction water to be metered on this project.
- d. If additional material storage is needed, there is room at the wastewater treatment plant for material storage. This must be coordinated with City staff.

**2) SPECIFICATIONS**

- a. Specification 03 05 61.10 – RockHardscp is an approved equal to Armorock Polymer Concrete for Polymer Concrete Manholes, provided that the manufacturer submits a written statement that the material meets or exceeds the design specifications, with the Contractor's bid.
- b. Specification 33 31 11 – The pump controller shall be a Flygt MultiSmart 3PC2Plus with all option modules installed.
- c. Specification 33 31 11 – SCADA will be provided to this site via a separate contract. The Auto Dialers shall be removed from this project.
- d. Specification 33 31 11 – Remove paragraph 2.3 B.7.f. A "No flow" or failure alarm shall be monitored and relayed by the SCADA system via a separate contract.

**Prepared by:**

---

**Bidder's Acknowledgment**

**JACOB | MARTIN**  
**TBPE Firm No. 2448**

---

**Date**